

# Request for proposal

**RE: Hastings Fire Department  
Bathroom Remodel**

**Address: 110 E. Mill St.  
Hastings, MI. 49058**

## **Main Men's Bathroom:**

- Remove Existing flooring, Installing new Vinyl Glue down Plank flooring.
- Remove Existing Partition Walls
- Remove Existing Toilet, Install New ADA toilet
- Tear down Dividing Block wall, as close to floor as possible.
- Install New lockset on door.
- Repaint walls
- Repaint existing large storage cabinet
- Install new Mirror (roughly 24"x36")
- Install new light fixture

## **Main ladies Restroom**

- Remove Existing flooring, Installing new Vinyl Glue down Plank flooring.
- Remove Existing Partition Walls
- Remove Existing Toilet, Install New ADA toilet
- Install New lockset on door.
- Repaint walls
- Install new Mirror (roughly 24"x36")

## **Back Bathroom**

- Remove Existing flooring, Installing new Vinyl Glue down Plank flooring.
- Remove Existing Partition Walls
- Remove Existing Toilet, Install New ADA toilet
- Install New Flat Panel Interior Door

- Install New lockset on door.
- Repaint walls
- Install new Mirror (roughly 24"x36")
- Remove Existing Shower and install new 36x36 Shower stall with door
- Frame new walls and finish with High Moisture Drywall if needed.